

Installation Instructions

Topanga, Vintner's, and Winemaker Floating Vanities

General Instructions:

CAUTION: Risk of personal injury. Native Trails Wall Mounts are extremely heavy, obtain sufficient help when lifting or moving.

CAUTION: Risk of property damage. Make sure that watertight seals exist on all drain connections, and that flooring, walls, and adjacent cabinetry are adequately protected while installing.

- It is strongly recommended that Native Trails wall mount vanities are installed by a licensed contractor.
- Observe all local plumbing and building codes.
- Have a licensed contractor determine if the wall is strong enough to adequately hold the weight of a full wall mount and applicable accessories.
- Ensure proper access to the final plumbing connections.
- Place a protective covering on the floor to prevent damage, unpack and inspect the wall mount for any damage.

Materials Recommended:

±8 - 4.5" Fastenmaster HeadLOK Heavy-Duty Flathead Fasteners Screws

Tools Needed:


Drill Measuring Tape Level

Pencil Stud Finder

- **1.** Mark the height and width of the vanity on the wall at the desired height in coordination with the location of the studs.
- **2.** Use a Level and attach French Cleat (B) to wall into the studs using at least two 4.5" screws per stud. (*Figure 1*)


Figure 1

F



- **3.** Hang vanity by connecting French Cleat (A) and French Cleat (B) securely into each other. Check with Level again and adjust slightly if needed.
- **4.** Install at least two 4.5" screws per stud through the vanity and into French Cleat (A) to secure the vanity to the studs. (*Figure 2*)

Figure 2



When cleaning up after installations, DO NOT USE ABRASIVE CLEANERS, as they may scratch and change the vanity surface.

Use warm water, a soft cloth and a non-abrasive soap to clean the surface.

Refer to the Care and Maintenance Instructions for more information.