General Instructions:

CAUTION: Risk of personal injury. Native Trails Wall Mounts are extremely heavy, obtain sufficient help when lifting or moving.

CAUTION: Risk of property damage. Make sure that watertight seals exist on all drain connections, and that flooring, walls, and adjacent cabinetry are adequately protected while installing.

- It is strongly recommended that Native Trails wall mount vanities are installed by a licensed contractor.
- Observe all local plumbing and building codes.

JATIVE RAILS

- Have a licensed contractor determine if the wall is strong enough to adequately hold the weight of a full wall mount and applicable accessories.
- Ensure proper access to the final plumbing connections.
- Place a protective covering on the floor to prevent damage, unpack and inspect the wall mount for any damage.

Materials Recommended:	Tools Needed:		
±8 - 4.5" Fastenmaster HeadLOK Heavy-Duty Flathead Fasteners Screws	Drill	Measuring Ta	ape Level
	Pencil Stud Finder		
 Mark the height and width of the vanity on the wall at the desired height in coordination with the location of the studs. 			Cleat (A) and French Cleat (E n Level again and adjust
2. Use a Level and attach French Cleat (B) to wall into the studs using at least two 4.5" screws per stud. (<i>Figure 1</i>)			tud through the vanity and anity to the studs. <i>(Figure 2</i>
Figure 1	Figure 2		
French Cleat (B) 4.5" Screws Wall Studs		French Cleat (A) French Cleat (B)	4.5" Screws Vanity

When cleaning up after installations, DO NOT USE ABRASIVE CLEANERS, as they may scratch and change the vanity surface. Use warm water, a soft cloth and a non-abrasive soap to clean the surface. Refer to the Care and Maintenance Instructions for more information.